



Park Hill School District

Building Successful Futures • Each Student • Every Day

2020 Pavement Repair Package - ADDENDUM #1

May 1, 2020

The following additions/changes/deletions shall be made and incorporated in the subject bid package:

Revision to Sheet 2:

With the exception of new basketball court surfacing at Plaza Middle School, all HMA Mix Design to be Type 3R. Plaza MS basketball courts may be fine graded commercial mix suitable for intended use.

Revision to Sheet 3:

Revised 'package one' completion requirement to paving substantial completion by June 15. Project close-out complete by June 30.

Revision to Sheet 4:

Revised 'package one' completion requirement to paving substantial completion by June 15. Project close-out complete by June 30.

Include unbolting, moving, storing on-site and re-bolting eight (8) picnic tables on basketball court (sealcoating) area.

Revisions to Sheet 5:

Incorporate the replacement of four (4) concrete bases at accessible parking stalls. Remove the bases and properly dispose, salvaging the existing signage. Install new 4-inch steel bollards encased in concrete. Paint bollards yellow and re-install existing signage a minimum of 60-inches above finished grade.



Park Hill School District

Building Successful Futures • Each Student • Every Day

Revisions to Sheet 7:

Patch 'E' to be by abutment milling and 2-inch HMA overlay omitting the full milling of the path.

Revision to Sheet 9:

Corrected 4-inch HMA Base replacement quantity to 419 SY.

Revision to Sheet 10:

Added incorporating with repaving the installation of a 12' x 24' 8-inch reinforced concrete dumpster pad in the southwest corner of the resurfacing area at the approach to dumpster.

Also included is the bid form.