

Park Hill South Sports High School Athletic Complex Renovation Riverside, MO

ADDENDUM #2 February 20, 2018

This addendum forms a part of the Contract Documents and modifies the original Bid Documents and Project Manual dated February 9, 2018.

Acknowledgement of the addendum is required in the Bid Form.

CLARIFICATIONS:

1. The pre-bid sign in list is attached.
2. The contractor is responsible for building a "bridge" over the track to protect the track material and asphalt from damage. The "bridge" will consist of a layered system of filter fabric, plywood or steel plates and soil or gravel. The contractor is responsible for building and removing the "bridge" in its entirety and cleaning the track as necessary for inspection prior to applying the new structural spray. More than one bridge may be built if the contractor desires.
3. The contractor is encouraged to photograph and/or video tape the existing conditions prior to commencing work.
4. All disturbed areas shall be seeded. The Owner will be responsible for grow-in.

CHANGES TO PROJECT MANUAL

1. Section 001010 – Remove and replace item, 1.07.B with the following:
 - B. Schedule requirements for each Option and Phase are outlined as follows:
 1. *Project site will be made available to the contractor immediately upon completion of the track and soccer season. The track will be made available May 24th and the Soccer field May 31. Mobilization and set-up will be allowed. Parking and Material storage will be coordinated with the District staff. In the event that teams or individuals do not qualify for further competition, the site may become available sooner.*
 2. *Substantial Completion shall be achieved on or before August 3, 2018, with Final Completion on or before August 10, 2018.*
2. Section 001010 – Remove item 1.08 Time Extensions for adverse weather.
3. Section 32 2200 – Remove in its entirety and replace with the attached section.
 - A. No maintenance equipment is required.
4. Section 32 2201 – Remove in its entirety and replace with the attached section.
 - A. No maintenance equipment is required.
 - B. 4 rolls of 15' x 75', with infill removed, shall be rolled and left on site for the Owners use. Coordinate location directly with Owners representative.
5. Section 32 2202 – Item 1.3.A.a: add "installation of new goal posts".

CHANGES TO DRAWINGS

1. SP0.00 – New location of spoil disposal site is illustrated on aerial view. See note 7 below.
2. SP0.01 - Long Jump Pit – The concrete curb on the northernmost runway, on the west edge of the east end long jump pit (nearest the take-off board) shall be saw-cut, removed and replaced with a similar concrete curb.
3. SP0.01 – Structural spray and re-stripe to be applied to Pole Vault runway and both long/triple jump runways
4. SP1.01 – The Play Clocks are a future item by Owner. 12" Quazite boxes are to be installed at each clock location, with the conduit terminating inside.
5. SP1.01 - The spoil area has moved to the northeast corner of the practice soccer field at the north end of the site.
6. SP1.01 – Combox has been removed from northwest corner of track.

7. SP2.01 - The spoil area has moved to the northeast corner of the practice soccer field at the north end of the site.
8. SP4.01 – Replace sheet in it's entirety and replace with the attached drawing:
 - A. Modify detail #1 to remove depth of soil stabilization (stabilization requirements are pending geo-tech investigation currently in process), revise subgrade slope to match the grading plan, and remove note about infield mix in line trench.
 - B. Graphic change illustrating concrete curb around shot put landing area.
 - C. Add detail #6 illustrating curb around shot put landing area.

END OF ADDENDUM 2