

Park Hill South Sports High School Athletic Complex Renovation Riverside, MO

ADDENDUM #3 February 22, 2018

This addendum forms a part of the Contract Documents and modifies the original Bid Documents and Project Manual dated February 9, 2018.

Acknowledgement of the addendum is required in the Bid Form.

CLARIFICATIONS:

1. The Geo-tech report is not complete. For bidding purposes, the soil stabilization alternate should be calculated using 12% fly-ash to a 12" depth, or 4% Portland cement to a 12" depth.
2. Conduit under to be bored under the track shall be modified to providing two (2) 1.5" diameter rolled pipe in two separate borings (four (4) conduit total). One will be used for power, the other for communication.

CHANGES TO PROJECT MANUAL

1. N/A

CHANGES TO DRAWINGS

1. SP1.01 – See clarification of conduit in Clarifications above.

END OF ADDENDUM 3